No.	Items of work	Quantity	Per unit	Rate
				Rs. as. p.
23	Re-roofing the existing Mangalore tiles on teak reepers with necessary work in verandah portions now proposed.	33·74	Sqr.	
24	New teak reepers in place of damaged ones ...	1,000	R.ft.	
25	New Mangalore tiles Do ...	500	1,000	
26	Boring holes in walls to fix rafters	80	Each	
27	Plastering with mortar to walls	322·00	Sqr.	
28	White and colour washing 2 coats	322·00	,,	
29	Flooring with 1½" thick cudapah slabs on 6" thick available brick bats jelly concrete in mortar with cement pointing, etc.	64·00	,,	
30	Wood work old re-fixing the old rafters and purline after sawing and cutting to size and planning, etc., complete to roof.	602·31	S.ft.	
31	Chocolate painting 3 coats	32·00	S.qr.	
32	Wood oiling 3 coats	25·00	,,	
33	Tarring to wood work	20·00	,,	
34	Roofing with 1st Class Mangalore tiles on 2" x 1" teak reepers nails, etc., complete.	45·00	,,	
35	Roofing with 1st Class Mangalore existing tiles and reepers.	64·80	,,	
36	New teak reepers in place of damaged ones ...	3,500	1,000 R.ft.	
37	New Mangalore tiles in place of damaged ones ...	4,200	1,000	
38	New Ridge tiles set in mortar	62	R.ft.	
39	Old Do do	242	,,	
40	Binding wall with burnt brick in clay and chunam plastering, etc., complete.	148	,,	
41	Washing the existing Mangalore tiles in smoked portions and colour wash, etc., complete.	98·62	Sqr.	
42	Dismantling the existing V shaped drain and removing the debris to far off.	Lump	sum	
43	Re-placing the existing box drain with necessary materials.	Lump	sum	
44	Unforeseen items of work while execution if found necessary.	Lump	sum	
45	Temporary supervision charges	Lump	sum	
46	Teakwood eve board	1,020	R.ft.	
47	Do gates	2	No.	

H. R. VENKATASUBBA RAO,
Executive Engineer.

KOLAR DIVISION.

Notice dated 24th December 1928.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part VI, pages 25—26, calling for tenders for restoring Geraddi Tank, Regd., No. 48 of Sidlaghatta Taluk. Last date of tender, 24th January 1929.

Notice dated 26th December 1928.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part VI, pages 5—6, calling for tenders for restoring Rampur Ramasayi Tank, Regd. No. 40 of Goribidnur Taluk. Last date of tender is 29th January 1929.

Dated 30th December 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 2 p.m. of 29th January 1929, for restoring Settinaikanahalli Melinkere Registered No. 353, Sidlaghatta Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A. M. to 5 P.M.

3 Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different irems specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 One hundred and fifty, in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Settinaikanahalli Melinkere, Sidlaghatta Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in figures and words.

10. The tenderers stating that the work would be executed at a certain percentage in excess or lower than the estimate will not be accepted.

Abstract estimate for restoring Settinayakanahalli Melinkere Tank, Registered No. 353 of Sidlaghatta Taluk.

Items of work	Per	Quantity	Rate	Cost	Total
Bund.			Rs. a. p.		
Clearing jungle including cutting of trees and removal of roots and removal of ant-hills ...	Grade	13			
Earthwork to bund with watering and tamping with lead and lift...	Cyd.	2,555			
Turfing	Syd.	2,417			
Cutting grips	Cyd.	325			
New stone revetment including lead of 3 miles	,,	555			
Removing and resetting old stone revetment	,,	239			
Providing grade and index stones with chistling painting etc., complete	Each	14			
Do. B. M. stones do ...	,,	2			
Do Gauge stone do ...	,,	1			
Do Registered No. stone ...	,,	1			

Items of work	Per	Quantity	Rate	Cost	Total
Sluice at R. L. 54·50.			Rs. a. p.		
Earthwork	Cyd.	97			
Concrete in surki mortar ...	C.ft.	121			
Burnt brick in surki mortar ...	,,	384			
Burnt stone slabs of 6″ thick ...	Sq. ft.	211			
Boring holes in slabs ...	Each	3			
Plastering with surki mortar ...	Sqr.	5·16			
Providing wooden plug with iron rod and locking arrangements ...	L. S.	...			
Earthwork refilling with watering and tamping complete ..	Cyd.	97			
Waste weir.					
Earthwork	,,	140			
Concrete in surki mortar ...	C.ft.	331			
Burnt brick in surki mortar ...	,,	582			
Burnt stone slabs dressed (6″) thick...	Sp.ft.	490			
Plastering with surki mortar ...	Sqr.	7·74			
New rough stone work with a lead from 1 to 3 miles ...	Cyd.	98			
Total ..	...	...	...	...	...
Contingencies ...	...	...	...	...	...
Grand Total ...	...	...	...	...	...

N. LAKSHMINARASIMHAIYA,
Executive Engineer

TUMKUR DIVISION.

Notice dated 5th January 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 26th January 1926 for putting railings on the bund of Ramapur Tank, Koratagere Taluk on Koratagere-Bychtapur Road. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of August 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

(3) (a) Percentages less or above estimated rates will not be accepted.

4. Each tender must be accompanied by a deposit of rupees three hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for putting railings on the bund of Rampur Tank, Koratagere Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.